

**QUOTATION REFERENCE NO.:**

**DATE OF QUOTATION:**

**Project Title:**

Sub-Contract Work:

**Bill of Quantities For**

Item no.	Description	Unit	Quantity	Rate	Amount in RM
1	Mobilization & demobilization of plant and equipment for the work	LS			
2	Provide temporary works such as dewatering, access within work area for supervision & installation and safety signage & measures for the excavated pit. Shoring work with steel sheet piles and strutting is excluded.	LS			
3	Excavate with suitable excavated material, level and compact, and surplus excavated material cart away, deposit and level at designated areas within site.	m <sup>3</sup>			
4	Backfill with compact sand bedding and surround OSD Tank	m <sup>3</sup>			
5	Backfill with original earth, surround and top of the tank and other structure if required.	m <sup>3</sup>			
6	Supply and install of EcoClean Ausdrain Enviromodule Tank	Box			
7	Assemble, stack and fix in positions the Enviro Modules to form the tank as per proposal drawings. (Machinery by main con)	Box			
8	Supply, install 1 layer of HDPE liner of 1.5mm thick as water proofing wrapped around Modular Tank (RWH)	m <sup>2</sup>			
9	Supply, install 1 layer of non woven Geotextile wrapped around Modular Tank (OSD)	m <sup>2</sup>			
10	Supply and install in position the CDS XXX as per proposal drawings	m <sup>3</sup>			
11	Supply, lay and fix in position as shown in shop drawings the 200mm diameter inlet and outlet drainage pipes.	Lot			
12	Supply & Install inlet and outlet Manhole	Lot			
13	Supply and Install od Maximesh Screen no.1	Lot			
14	Supply and install of submersible pump (RWH)	Lot			
	<b>TOTAL AMOUNT FOR QUOTATION</b>				